

**City of Roswell - Myrtle Street/Zion Circle Permeable Paver Installation
Bid Form for Additive Alternate No. 1**

Item No.	Description	Est. Qty.	Unit	Unit Cost (\$)	Total Cost (\$)
Construction Facilities and Site Preparation					
2	Orange Barrier Fence	210	LF		
Erosion and Sediment Control					
3	Temporary Silt Fence – Type NS	100	LF		
Demolition/Earthwork/Paver System					
5	Pavement/Curb/Subbase Removal (8-inch depth, in-place)	2,200	CF		
6	Excavation and compaction of subgrade (earthwork only - includes excavation, compaction, final grading, disposal of excess)	280	CY		
7	Permeable Paver System Complete (3-1/8-inch Concrete Paver, aggregate in openings, 2-inch bedding material, 6-inch stone base, 24-inch gravel reservoir)	2,880	SF		
10	6-inch PVC Underdrain	160	LF		
11	Geotextile partial stop (barrier) in reservoir stone	2	EA		
Allowances					
14	Additional Items	1	LS	--	2,500.00
				TOTAL AMOUNT:	

Note - Additive Alternative Bid includes all work included in "Bid Additive Alternative No. 1" as delineated on Sheet C-3.
The City may elect to add this portion of work to the base bid.