

**City of Roswell - Myrtle Street/Zion Circle Permeable Paver Installation
Bid Form - Base Bid**

Item No.	Description	Est. Qty.	Unit	Unit Cost (\$)	Total Cost (\$)
Construction Facilities and Site Preparation					
1	Mobilization and Demobilization (includes MOT, construction sign, and warranty)	1	LS	--	
2	Orange Barrier Fence	750	LF		
Erosion and Sediment Control					
3	Temporary Silt Fence – Type NS	100	LF		
4	Curb Inlet Protection	2	EA		
Demolition/Earthwork/Paver System					
5	Pavement/Curb/Subbase Removal (8-inch depth, in-place)	6,400	CF		
6	Excavation and compaction of subgrade (earthwork only - includes excavation, compaction, final grading, disposal of excess)	840	CY		
7	Permeable Paver System Complete (3-1/8-inch Concrete Paver, aggregate in openings, 2-inch bedding material, 6-inch stone base, 24-inch gravel reservoir)	9,500	SF		
8	6-inch Concrete Curb	280	LF		
9	6-inch Concrete Header Curb Barrier	65	LF		
10	6-inch PVC Underdrain	450	LF		
11	Geotextile partial stop (barrier) in reservoir stone	11	EA		
Landscaping					
12	Temporary Mulching	0.25	AC		
13	Sodding (Bermuda grass)	1,200	SF		
Allowances					
14	Additional Items	1	LS	--	10,000.00
TOTAL AMOUNT:					

Note - Base Bid includes all work identified in "Limits of Work for Base Bid" delineated on Sheet C-3.