


CONSTRUCTION PLANS FOR: CITY OF ROSWELL, GEORGIA

RECEIVED
AUG 28 2017
COMM DEV-ROSWELL

SHEET NUMBER	SHEET TITLE
-	COVER SHEET
1	LEGEND, ABBREVIATIONS, AND NOTES
2	SITE PLAN 1
3	SITE PLAN 2
4	STANDARD DETAILS 1
5	STANDARD DETAILS 2
6	EROSION CONTROL NOTES
7	EROSION CONTROL DETAILS




PROJECT VICINITY MAP



PROJECT:

MILLBROOK CIRCLE WATER MAIN REPLACEMENT



PROJECT LOCATION MAP

CONSULTING ENGINEER:


ESI

ENGINEERING STRATEGIES, INC.

Phone: (770) 429-0001

AUGUST 2017

Approved Date 8/23/17
Plans Reviewer



24-HOUR CONTACT
CHRIS BOYD (770) 817-6750

RESUBMITTAL
ENGINEERING #1


Millbrook Cir

201703534


CONSTRUCTION PLANS FOR: CITY OF ROSWELL, GEORGIA

RECEIVED
AUG 28 2017
COMM DEV-ROSWELL

SHEET NUMBER	SHEET TITLE
-	COVER SHEET
1	LEGEND, ABBREVIATIONS, AND NOTES
2	SITE PLAN 1
3	SITE PLAN 2
4	STANDARD DETAILS 1
5	STANDARD DETAILS 2
6	EROSION CONTROL NOTES
7	EROSION CONTROL DETAILS



PROJECT VICINITY MAP



PROJECT LOCATION MAP

PROJECT: MILLBROOK CIRCLE WATER MAIN REPLACEMENT

CONSULTING ENGINEER:

ESI

ENGINEERING STRATEGIES, INC.

Phone: (770) 429-0001

AUGUST 2017



24-HOUR CONTACT
CHRIS BOYD (770) 817-6750

SUBMITTAL
ENGINEERING #1

Millbrook Cir

201703534

THE HOLDER OF THIS DOCUMENT WAIVES ALL CLAIMS AGAINST ESI FOR ANY UNAUTHORIZED CHANGES OR REUSE OF THIS DOCUMENT. THIS DOCUMENT IS AN INSTRUMENT OF SERVICE OF ENGINEERING STRATEGIES, INC. WHO RETAINS ALL RIGHTS OF COMMON LAW, STATUTE AND COPYRIGHT THERE TO.

STANDARD LINE TYPES

Table listing standard line types (e.g., EXISTING CONTOUR - MAJOR, PROPOSED CONTOUR - MAJOR) with corresponding line symbols.

STANDARD HATCH PATTERNS

Table listing standard hatch patterns (e.g., ASPHALT RESURFACE, EXISTING ASPHALT PAVEMENT) with corresponding hatch symbols.

STANDARD SYMBOLS

Table listing standard symbols (e.g., FIRE HYDRANT, YARD HYDRANT, VALVE - EXISTING) with corresponding symbols and descriptions.

ABBREVIATIONS

Table listing abbreviations (e.g., ACP ASBESTOS CEMENT PIPE, BF BUTTERFLY VALVE) with corresponding full names.

GENERAL CONSTRUCTION NOTES

- 1. ALL WATER LINE INFRASTRUCTURE SHALL BE INSTALLED USING CITY OF ROSWELL "STANDARD CONSTRUCTION SPECIFICATIONS AND SUBDIVISION REGULATIONS."
2. NO CONSTRUCTION ACTIVITIES SHALL BE CONDUCTED OUTSIDE OF THE RIGHT-OF-WAY. THERE IS LIMITED SPACE AVAILABLE FOR CONSTRUCTION STORAGE...

CITY OF ROSWELL STANDARD CONSTRUCTION NOTES

- 1. DRIVEWAYS SHALL BE CONSTRUCTED OF CONCRETE AND SLOPED PER GEORGIA HIGHWAY STANDARD 9031-J. CURB SHALL NOT BE BROKEN FROM GUTTER. CURB AND GUTTER TO BE REMOVED TO EXISTING CONSTRUCTION JOINT OR NEW JOINTS SAWS.
2. ALL SILT BARRIERS AND CONSTRUCTION ENTRANCE PADS MUST BE PLACED PRIOR TO ANY CLEARING AND/OR GRADING...


- 16. ANY PIPE, SOLDER OR FLUX USED IN THE INSTALLATION OR REPAIR OF THE WATER LINES MUST BE LEAD-FREE.
17. FRONT GATES ARE ALLOWED ON DUMPSTER PADS ONLY WITH PRIOR APPROVAL FROM THE PUBLIC WORKS DEPARTMENT.
18. ALL ROAD AND STORM STRUCTURES SHALL CONFORM TO GEORGIA DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATIONS.

CITY OF ROSWELL DEPARTMENT OF TRANSPORTATION NOTES

- 1. ALL PAVEMENT CUTS WIDER THAN FOUR (4) FEET SHALL BE REPAIRED BY A STANDARD CITY OF ROSWELL PAVEMENT SECTION, AS PER SECTION 2.2.1.C, PAVING, TABLE 2.11-PAVEMENT THICKNESS, OF THE CITY OF ROSWELL STANDARD CONSTRUCTION SPECIFICATIONS.
2. STREET CUTS
A. GENERAL
1) OPEN STREET CUTS ARE NOT PERMITTED WITHOUT APPROVAL FROM THE CITY OF ROSWELL DEPARTMENT OF TRANSPORTATION...

TREE PRESERVATION


- 1. UNLESS NOTED TO BE REMOVED, CONTRACTOR SHALL PROTECT ALL SPECIMEN TREES (2" AND LARGER HARDWOODS AND 30" AND LARGER SOFTWOODS.) ALL SPECIMEN TREES IDENTIFIED TO BE REMOVED AND ALL NON-SPECIMEN TREES THAT INTERFERE WITH THE INSTALLATION OF THE WATER LINE SHALL BE REMOVED BY THE CONTRACTOR...
2. WHEN DIGGING NEAR TREES, CONTRACTOR SHALL PRUNE ALL EXPOSED ROOTS 1-INCH IN DIAMETER OR LARGER ON THE SIDE OF THE TRENCH ADJACENT TO THE TREES...



ESI ENGINEERING STRATEGIES, INC. 3855 SHALLOWFORD ROAD, SUITE 525 MARIETTA, GA 30062 (770) 429-0001

Table with project information: PROJECT NUMBER, DATE (AUGUST 2017), REVISION, and a revision number table.

CITY OF ROSWELL, GEORGIA MILLBROOK CIR. WATER MAIN REPLACEMENT LEGEND, ABBREVIATIONS, AND NOTES




ESI
 ENGINEERING STRATEGIES, INC.
 3655 SHALLOWFORD ROAD, SUITE 525
 MARIETTA, GA 30062
 (770) 429-0001

PROJECT NUMBER: ---	DATE: AUGUST 2017
REVISION	DATE

DESIGN: ---
 DRAWN: ---
 CHECK: ---
BASE DIMENSIONS 1" LONG FOR SCALES SHOWN ON THIS SHEET. IF NOT 1" LONG ON THIS SHEET, ADJUST SCALES ACCORDINGLY.

CITY OF ROSWELL, GEORGIA
 MILLBROOK CIR. WATER MAIN REPLACEMENT
 SITE PLAN 1



SHEET NO.
 2



- NOTES:**
1. CONTRACTOR SHALL CONNECT ALL WATER METERS TO NEW WATER LINE WHETHER THEY ARE SHOWN ON THE DRAWINGS OR NOT.
 2. LONG SERVICE CONNECTIONS SHALL BE INSTALLED IN A 2" PVC CASING PIPE ACROSS ROADWAY.
 3. AFTER ROAD IS REPAIRED, CONTRACTOR SHALL RESTRIPE CROSSWALK, TURN LANE, AND ANY OTHER ROADWAY MARKINGS THAT ARE DAMAGED BY CONSTRUCTION. STRIPING SHALL BE IN ACCORDANCE WITH GDOT STANDARD SPECIFICATIONS.
 4. CONTRACTOR SHALL ADD SELECT FILL TO ERODED AREA BEHIND CURB AND SOD PER EASEMENT AGREEMENT. FINISHED GRADE SHALL SLOPE 2-PERCENT AWAY FROM BACK OF CURB. EXTENT OF FILL IS BETWEEN NORCROSS ROAD AND DRIVEWAY TO 20 FEET BEHIND BACK OF CURB.
 5. CONTRACTOR SHALL BORE UNDER DRIVEWAYS AND WALK WAYS.


MATCHLINE A

MATCHLINE A



NOTES:

1. CONTRACTOR SHALL CONNECT ALL WATER METERS TO NEW WATER LINE WHETHER THEY ARE SHOWN ON THE DRAWINGS OR NOT.
2. LONG SERVICE CONNECTIONS SHALL BE INSTALLED IN A 2" PVC CASING PIPE ACROSS ROADWAY.



ESI
 ENGINEERING STRATEGIES, INC.
 3855 SHALLLOWFORD ROAD, SUITE 525
 MARIETTA, GA 30062
 (770) 429-0001

PROJECT NUMBER: —	DATE: AUGUST 2017
REVISION	DATE
△	

DSGN:
 DRAWN:
 CHCK:
 648 BELOW IS 1" LONG FOR SCALES SHOWN ON THIS SHEET. IF NOT 1" LONG ON THIS SHEET, ADJUST SCALES ACCORDINGLY.

CITY OF ROSWELL, GEORGIA
 MILLBROOK CIR. WATER MAIN REPLACEMENT
 SITE PLAN 2

L:\Roswell\Millbrook Circle\DWG\Sheets\CS - Site Plan.dwg - 8/23/2017




ESI
ENGINEERING STRATEGIES, INC.
3855 SHALLOWFORD ROAD, SUITE 525
MARIETTA, GA 30062
(770) 429-0001

PROJECT NUMBER: —	DATE: AUGUST 2017
REVISION	DATE


DESIGN: _____
DRAWN: _____
CHECK: _____
BAR RELIEFS 1" LONG FOR SCALES SHOWN ON THIS SHEET. IF NOT 1" LONG ON THIS SHEET, ADJUST SCALES ACCORDINGLY.

CITY OF ROSWELL, GEORGIA
MILLBROOK CIR. WATER MAIN REPLACEMENT
STANDARD DETAILS 1


SHEET NO. 4




CITY OF ROSWELL WATER UTILITY STANDARD DETAIL
ROS WELL Water Utility Essential & Life & Source
TYPICAL WATER LINE LOCATION
REVISED: 12/29/2011
DETAIL NO. **W01**




CITY OF ROSWELL WATER UTILITY STANDARD DETAIL
ROS WELL Water Utility Essential & Life & Source
PIPE BEDDING DETAIL
REVISED: 12/29/2011
DETAIL NO. **W02A**




CITY OF ROSWELL WATER UTILITY STANDARD DETAIL
ROS WELL Water Utility Essential & Life & Source
TRENCH REPAIR DETAIL
REVISED: 12/29/2011
DETAIL NO. **W02B**




CITY OF ROSWELL WATER UTILITY STANDARD DETAIL
ROS WELL Water Utility Essential & Life & Source
TRENCH REPAIR DETAIL
REVISED: 12/29/2011
DETAIL NO. **W02C**




CITY OF ROSWELL WATER UTILITY STANDARD DETAIL
ROS WELL Water Utility Essential & Life & Source
FIRE HYDRANT DETAIL
REVISED: 12/29/2011
DETAIL NO. **W03**



CITY OF ROSWELL WATER UTILITY STANDARD DETAIL
ROS WELL Water Utility Essential & Life & Source
SERVICE SADDLE DETAIL
REVISED: 12/29/2011
DETAIL NO. **W04**



CITY OF ROSWELL WATER UTILITY STANDARD DETAIL
ROS WELL Water Utility Essential & Life & Source
TAPPING SLEEVE DETAIL
REVISED: 12/29/2011
DETAIL NO. **W05**



CITY OF ROSWELL WATER UTILITY STANDARD DETAIL
ROS WELL Water Utility Essential & Life & Source
CONCRETE VALVE MARKER DETAIL
REVISED: 12/29/2011
DETAIL NO. **W06**

RESTRAINED JOINT GLAND (TYP.)
90° EYE-BOLT (TYP.)
3/4" THREADED ROD (TYP.)

FITTING WITH TIE-RODS AND RESTRAINED JOINT GLANDS

FITTING WITH RESTRAINED JOINT GLAND AND THRUST BLOCK

TIE-RODS FROM RESTRAINED JOINT GLAND TO RESTRAINED JOINT GLAND

PUSH-ON JOINT WITH RESTRAINED JOINT GASKET

PIPE DIA. (IN)	ROD SIZE (IN)	MINIMUM # OF RODS
6	3/4"	2
8	3/4"	2
10	3/4"	2
12	3/4"	2
14	3/4"	4
16	3/4"	4

TIE-ROD CHART

NOTES:

- RESTRAINED JOINT LENGTHS SHALL BE CALCULATED BY THE DESIGN ENGINEER.
- ALL FITTINGS SHALL HAVE TWO FORMS OF RESTRAINT (I.E. THRUST BLOCK + RESTRAINED JOINT GLANDS, RESTRAINED JOINT GLANDS + THREADED RODS, THRUST BLOCK + THREADED RODS).
- FITTINGS LOCATED WITHIN 5 FEET OF EACH OTHER SHALL BE TIED TOGETHER WITH THREADED ROD.
- THREADED RODS AND 90° EYE BOLTS SHALL BE TYPE 316 HARDENED STAINLESS STEEL CONFORMING TO ASTM A193, GRADE B8M, CLASS 2; NUTS SHALL BE TYPE 316 STAINLESS STEEL CONFORMING TO ASTM A194, GRADE 8M; AND WASHERS SHALL BE 316 STAINLESS STEEL FLAT WASHERS.

CITY OF ROSWELL WATER UTILITY STANDARD DETAIL

ROSWELL Water Utility
Essential to Life & Source

VALVE AND FITTING THRUST RESTRAINT

REVISED: 12/29/2011
DETAIL NO. **W08**

PIPE DIA. (IN)	A DIM.	B DIM.	C DIM.	MINIMUM BEARING AREA (FT ²)	TOTAL BLOCK AREA (FT ²)	CONC. VOLUME (YD ³)	THRUST (LBF)
4	1'-6"	3'-0"	1'-6"	2.04	4.50	0.24	4,072
6	2'-0"	4'-0"	1'-6"	4.21	8.00	0.43	8,413
8	2'-5"	4'-10"	1'-6"	7.24	11.68	0.62	14,473
10	2'-11"	5'-10"	1'-6"	10.89	17.01	0.91	21,773
12	3'-5"	6'-10"	2'-0"	15.40	23.35	1.66	30,791
14	3'-10"	7'-8"	2'-0"	20.68	29.39	2.08	41,387
16	4'-4"	8'-8"	2'-0"	26.75	37.56	2.66	53,502

NOTES:

- THRUST COLLAR DIMENSIONS ARE BASED ON THE FOLLOWING DESIGN CRITERIA.
WORKING PRESSURE = 150 PSI
SOIL BEARING CAPACITY = 2,000 PSF
SAFETY FACTOR = 1.5
THESE ARE THE MINIMUM DESIGN CRITERIA. IF ACTUAL WORKING PRESSURE IS GREATER THAN 150 PSI OR IF ACTUAL SOIL BEARING CAPACITY IS LESS THAN 2,000 PSF, DIMENSIONS SHALL BE RECALCULATED.
- THRUST COLLAR CONCRETE SHALL HAVE A MINIMUM 28 DAY COMPRESSIVE STRENGTH OF 3,000 PSI.
- THRUST COLLAR SHALL BE WELDED ON BY DUCTILE IRON PIPE MANUFACTURER. ALTERNATIVELY, A RESTRAINED JOINT GLAND MAY BE USED.
- THRUST COLLAR BEARING AREA SHALL BEAR AGAINST UNDISTURBED SOIL. BACKFILL THAT IS PLACED AGAINST THRUST COLLAR (NON-BEARING AREAS) SHALL BE COMPACTED TO MINIMUM 95 PERCENT AASHTO T-99-49 PROCTOR CURVE.

CITY OF ROSWELL WATER UTILITY STANDARD DETAIL

ROSWELL Water Utility
Essential to Life & Source

CONCRETE THRUST COLLAR DETAIL

REVISED: 12/29/2011
DETAIL NO. **W09**

TEES AND DEAD-ENDS

PIPE DIA. (IN)	D DIM.	L DIM.	H DIM.	W DIM.	CONC. VOLUME (YD ³)	THRUST (LBF)
4	0'-6"	2'-2"	1'-1"	10	0.54	4,072
6	0'-8"	3'-0"	1'-6"	1'-2"	0.12	8,413
8	0'-10"	3'-10"	1'-11"	1'-6"	0.25	14,473
10	1'-0"	4'-8"	2'-4"	1'-10"	0.45	21,773
12	1'-2"	5'-8"	2'-10"	2'-3"	0.81	30,791
14	1'-4"	6'-8"	3'-3"	2'-7"	1.22	41,387
16	1'-6"	7'-4"	3'-8"	2'-11"	1.78	53,502

90° BENDS

PIPE DIA. (IN)	D DIM.	L DIM.	H DIM.	W DIM.	CONC. VOLUME (YD ³)	THRUST (LBF)
4	0'-6"	2'-5"	15	12	0.07	5,758
6	0'-8"	3'-5"	1'-9"	1'-9"	0.19	11,895
8	0'-10"	4'-8"	2'-4"	1'-11"	0.46	20,488
10	1'-0"	5'-8"	2'-10"	2'-4"	0.82	30,792
12	1'-2"	6'-8"	3'-4"	2'-9"	1.33	43,545
14	1'-4"	7'-8"	3'-10"	3'-2"	2.02	58,502
16	1'-6"	8'-10"	4'-8"	3'-8"	3.10	75,683

45° BENDS

PIPE DIA. (IN)	D DIM.	L DIM.	H DIM.	W DIM.	CONC. VOLUME (YD ³)	THRUST (LBF)
4	0'-6"	1'-10"	11	8	0.03	3,116
6	0'-8"	2'-8"	1'-4"	1'-0"	0.08	6,435
8	0'-10"	3'-4"	1'-9"	1'-3"	0.16	11,077
10	1'-0"	4'-2"	2'-1"	1'-7"	0.32	18,664
12	1'-2"	5'-0"	2'-6"	1'-11"	0.55	23,566
14	1'-4"	6'-0"	2'-10"	2'-2"	0.89	31,681
16	1'-6"	6'-8"	3'-3"	2'-6"	1.20	40,949

22 1/2° BENDS

PIPE DIA. (IN)	D DIM.	L DIM.	H DIM.	W DIM.	CONC. VOLUME (YD ³)	THRUST (LBF)
4	0'-6"	1'-4"	8	5	0.01	1,589
6	0'-8"	1'-10"	0'-7"	0'-2"	0.02	3,283
8	0'-10"	2'-5"	1'-3"	0'-10"	0.06	5,847
10	1'-0"	3'-0"	1'-6"	1'-0"	0.11	8,495
12	1'-2"	3'-6"	1'-9"	1'-2"	0.18	12,014
14	1'-4"	4'-2"	2'-1"	1'-5"	0.30	18,141
16	1'-6"	4'-8"	2'-4"	1'-7"	0.42	20,875

NOTES:

- THRUST BLOCK DIMENSIONS ARE BASED ON THE FOLLOWING DESIGN CRITERIA.
WORKING PRESSURE = 150 PSI
SOIL BEARING CAPACITY = 2,000 PSF
SAFETY FACTOR = 1.5
THESE ARE THE MINIMUM DESIGN CRITERIA. IF ACTUAL WORKING PRESSURE IS GREATER THAN 150 PSI OR IF ACTUAL SOIL BEARING CAPACITY IS LESS THAN 2,000 PSF, DIMENSIONS SHALL BE RECALCULATED.
- THRUST BLOCK CONCRETE SHALL HAVE A MINIMUM 28 DAY COMPRESSIVE STRENGTH OF 2,500 PSI.
- THRUST BLOCK SHALL BEAR AGAINST UNDISTURBED SOIL.
- A MINIMUM 10 MIL PLASTIC SHEET SHALL BE PLACED BETWEEN CONCRETE AND PIPE.
- ALL BOLTS SHALL REMAIN ACCESSIBLE. DO NOT COVER WITH CONCRETE.

CITY OF ROSWELL WATER UTILITY STANDARD DETAIL

ROSWELL Water Utility
Essential to Life & Source

CONCRETE THRUST BLOCK DETAIL

REVISED: 12/29/2011
DETAIL NO. **W10**

NOTES:

- WATER METER WILL BE PROVIDED AND INSTALLED BY THE CITY OF ROSWELL. CONTRACTOR SHALL PROVIDE ALL OTHER APPURTENANCES.

CITY OF ROSWELL WATER UTILITY STANDARD DETAIL

ROSWELL Water Utility
Essential to Life & Source

3/4" WATER METER INSTALLATION

REVISED: 12/29/2011
DETAIL NO. **W11**



ESI
ENGINEERING STRATEGIES, INC.
3855 SHALLOWFORD ROAD, SUITE 525
MARIETTA, GA 30062
(770) 429-0001

PROJECT NUMBER: —

DATE:	REVISION
AUGUST 2017	

DSGN: —
DRWN: —
CHK: —

BAR BELOCIS 1" LONG FOR SCALES SHOWN ON THIS SHEET. IF NOT 1" LONG ON THIS SHEET, ADJUST SCALES ACCORDINGLY.

CITY OF ROSWELL, GEORGIA
MILLBROOK CIR. WATER MAIN REPLACEMENT
STANDARD DETAILS 2

CITY OF ROSWELL STANDARD EROSION AND SEDIMENT CONTROL NOTES

1. THE CONSTRUCTION PAD SHALL BE MAINTAINED IN A CONDITION THAT WILL PREVENT TRACKING OR FLOW OF MUD ONTO PUBLIC STREETS.
2. SILT FENCES AND HAY BALE BARRIERS SHALL BE CLEANED OR REPLACED AND MAINTAINED IN FUNCTIONAL CONDITION UNTIL PERMANENT EROSION CONTROL MEASURES ARE ESTABLISHED.
3. SILT FENCE FABRIC SHALL BE COMPRISED OF GEORGIA DEPARTMENT OF TRANSPORTATION QUALIFIED PRODUCTS SECTION 171, TYPE "S," FOR SILT FENCE FABRIC. TYPE "NS" SILT FENCE FABRIC AND CONSTRUCTION MAY BE ALLOWED WITH PRIOR WRITTEN APPROVAL FROM THE LAND DEVELOPMENT INSPECTOR.
4. ALL GRASSING SHALL BE IN ACCORDANCE WITH CHAPTER 6, SECTION III "VEGETATIVE PRACTICES" OF THE MANUAL FOR EROSION AND SEDIMENT CONTROL IN GEORGIA.
5. ALL OTHER WORK SHALL BE PERFORMED IN ACCORDANCE WITH THE SPECIFICATIONS OF THIS SAME MANUAL.
6. THE CONTRACTOR SHALL FURNISH THE CITY OF ROSWELL ENGINEERING DIVISION WITH A SCHEDULE OF ANTICIPATED STARTING AND COMPLETION DATES FOR EACH SEQUENCE OF LAND DISTURBING ACTIVITY LISTED IN ITEMS ONE THROUGH FIVE ABOVE.
7. EROSION CONTROL DEVICES WILL BE IN PLACE BEFORE SITE DISTURBANCE AND WILL BE PERIODICALLY INSPECTED AND REPAIRED OR RESTORED AS NEEDED TO FUNCTION PROPERLY UNTIL PERMANENT MEASURES ARE ESTABLISHED AND PROJECT IS COMPLETE, I.E. CONSTRUCTION EXITS SHALL BE REDRESSED OR CLEANED AS SILT REDUCES THEIR EFFECTIVENESS.
8. ANY ADDITIONAL CONSTRUCTION OTHER THAN SHOWN ON THIS PLAN WILL REQUIRE ADDITIONAL EROSION AND SEDIMENT CONTROL MEASURES AND PRIOR APPROVAL FROM THE CITY OF ROSWELL ENGINEERING DIVISION.
9. TEMPORARY VEGETATION AND/OR HEAVY MULCH WILL BE USED TO STABILIZE AREAS. IN NO CASE SHALL A SITE BE LEFT BARE FOR MORE THAN SEVEN (7) DAYS.
10. ALL DISTURBED AREAS WILL BE PERMANENTLY LANDSCAPED AND GRASSED AS QUICKLY AS POSSIBLE.
11. ADDITIONAL MEASURES MAY BE REQUIRED TO CONTROL EROSION AS DETERMINED NECESSARY BY CITY INSPECTORS.
12. PERSON RESPONSIBLE FOR EROSION CONTROL MEASURES IS: CHRIS BOYD. EMERGENCY #: (770) 841-3715.
13. EROSION CONTROL MATTING AND BLANKETS SHALL BE USED ON ALL SLOPES EXCEEDING 3:1.
14. ALL APPLICATIONS OF HYDROSEED WILL BE FOLLOWED BY 1/2" TO 1" MULCH.
15. SITES OVER 5 ACRES MUST PREPARE MULTI-STAGE EROSION CONTROL PLAN.
16. NO CLEARING BEYOND THE LIMITS OF DISTURBANCE SHOWN ON THE APPROVED PLANS SHALL BE ALLOWED.
17. NO LAND DISTURBING ACTIVITY WITHIN ANY TREE SAVE AREA SHALL BE ALLOWED.
18. POLYMERS MUST BE USED ON ALL DISTURBED AREAS INCLUDING PARKING LOTS.
19. THE PROPERTY OWNER AND CONTRACTOR ARE EQUALLY RESPONSIBLE FOR ALL EROSION CONTROL ACTIVITIES.
20. NOTICE IS HEREBY GIVEN THAT ALL EROSION AND SEDIMENT DEVICES AND PRACTICES MUST BE INSTALLED AND MAINTAINED AT ALL TIMES. NO FURTHER NOTICE WILL BE GIVEN. ANY SITE UPON WHICH THE LAND DEVELOPMENT INSPECTOR FINDS ANY DEFICIENCY WILL BE SUBJECT TO AN IMMEDIATE ENFORCEMENT ACTION WITHOUT WARNING.
21. EROSION AND SEDIMENT CONTROL DEVICES MUST BE MAINTAINED IN A SATISFACTORY CONDITION 24 HOURS A DAY, 7 DAYS A WEEK.
22. ALL BEST MANAGEMENT PRACTICES SHALL BE JUDGED NOT ON APPEARANCES BUT PERFORMANCES ONLY.
23. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO OBTAIN QUALIFIED PROFESSIONAL ADVICE WHEN QUESTIONS ARISE CONCERNING DESIGN AND EFFECTIVENESS OF EROSION CONTROL DEVICES, NOT THE CITY OF ROSWELL.
24. EROSION CONTROL DEVICES THAT ARE INSTALLED AS DIRECTED BY THE LAND DEVELOPMENT INSPECTOR BUT NOT SHOWN ON THE APPROVED PLAN AND WHICH ALSO SUBSEQUENTLY FAIL ARE THE RESPONSIBILITY OF THE CONTRACTOR.
25. ALL TEMPORARY AND PERMANENT SEEDING MUST BE PERFORMED AT THE APPROPRIATE SEASON. ADDITIONAL PLANTINGS WILL BE NECESSARY IF A SUFFICIENT STAND OF GRASS FAILS TO GROW.
26. THE LAND DEVELOPMENT INSPECTOR WILL DETERMINE ADEQUATE COVER OF NEW PLANTINGS.
27. TOPSOIL SHALL BE STOCKPILED AND USED TO DRESS FINAL GRADES.
28. NO DISTURBANCE WILL BE ALLOWED WITHIN FLOOD PLAINS OR WETLANDS.
29. EROSION CONTROL MEASURES WILL BE MAINTAINED AT ALL TIMES. ADDITIONAL EROSION AND SEDIMENT CONTROL MEASURES WILL BE NECESSARY IF DEEMED BY ON-SITE INSPECTION.
30. SILT FENCING MUST BE MIRAFI 100x FABRIC, OR EQUIVALENT SUBSTITUTE. MARIFAX 100x SPECIFICATIONS: MINIMUM WIDTH OF 36", MULLEN BURST STRENGTH OF 200 P.S.I., TRAPEZOIDAL TEAR STRENGTH OF 65 LBS., EQUIVALENT OPENING SIZE OF #40 U.S. STANDARD SIEVE AND GRAB STRENGTH OF 120 LBS.
31. SILT FENCE SHALL NOT BE PLACED IN STREAM BUFFER OR FLOOD PLAINS.
32. WHEN SILT FENCES BECOME 1/3 FULL OF SEDIMENT, THE SEDIMENT MUST BE REMOVED.

THE CONTRACTOR SHALL FURNISH WEEKLY REPORTS TO THE CITY, WHICH INDICATES THE DATE, PERSON RESPONSIBLE, AND NOTATION OF ALL DEFICIENCIES AND CORRECTIONS MADE TO ALL EROSION AND SEDIMENT CONTROL DEVICES.
33. THE ESCAPE OF SEDIMENT FROM THE SITE SHALL BE PREVENTED BY THE INSTALLATION OF EROSION AND SEDIMENT CONTROL MEASURES AND PRACTICES PRIOR TO, OR CONCURRENT WITH, LAND DISTURBING ACTIVITIES.
34. EROSION CONTROL MEASURES WILL BE MAINTAINED AT ALL TIMES. IF FULL IMPLEMENTATION OF THE APPROVED PLAN DOES NOT PROVIDE FOR EFFECTIVE EROSION CONTROL, ADDITIONAL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE IMPLEMENTED TO CONTROL OR TREAT THE SEDIMENT SOURCE.
35. ANY DISTURBED AREA LEFT EXPOSED FOR A PERIOD GREATER THAN 14 DAYS SHALL BE STABILIZED WITH MULCH OR TEMPORARY SEEDING.
36. NON-EXEMPT ACTIVITIES SHALL NOT BE CONDUCTED WITHIN THE 25 OR 50-FOOT UNDISTURBED STREAM BUFFERS AS MEASURED FROM THE POINT OF WRESTED VEGETATION WITHOUT FIRST ACQUIRING THE NECESSARY VARIANCES AND PERMITS.
37. ACCORDING TO THE GEORGIA STORMWATER MANAGEMENT MANUAL (BLUE BOOK) TABLE 2.1.4-2, THE ESTIMATED RUNOFF COEFFICIENT FOR SINGLE FAMILY RESIDENTIAL AREAS IS 0.50. BECAUSE THE CONSTRUCTION OF THIS PROJECT WILL BE IN THE RIGHT-OF-WAY AND IN GRASSY AREAS AND ALL GRASSY AREAS DISTURBED BY TRENCHING ACTIVITIES WILL BE RETURNED TO GRASS AFTER CONSTRUCTION, THE FLOW REGIME UNCHANGED. THE ESTIMATED POST CONSTRUCTION RUNOFF COEFFICIENT IS ALSO 0.50.
38. THE RECEIVING WATER FOR THIS PROJECT IS HOG WALLOW CREEK.
39. PROVIDE BMPs FOR THE REMEDIATION OF ALL PETROLEUM SPILLS AND LEAKS.

GENERAL EROSION AND SEDIMENT CONTROL NOTES

1. THIS PROJECT IS LOCATED IN LAND LOTS 451 AND 452 IN THE CITY OF ROSWELL, GEORGIA AND CONSISTS OF INSTALLING APPROXIMATELY 525 LINEAR FEET OF 8-INCH DUCTILE IRON PIPE WATER LINE AND APPROXIMATELY 800 LINEAR FEET OF 2-INCH POLYETHYLENE WATER LINE IN AND AROUND MILLBROOK CIRCLE. THE NEW WATER LINE WILL REPLACE AN EXISTING 2-INCH GALVANIZED STEEL WATER LINE. THE NEW WATER LINE WILL TIE INTO AN EXISTING 12-INCH DIP WATER LINE AT THE INTERSECTION OF MILLBROOK CIRCLE AND NORCROSS STREET.
2. THE TOTAL PROJECT AREA IS APPROXIMATELY 36,250 SQUARE FEET (0.83 ACRES). THE TOTAL DISTURBED AREA FOR THIS PROJECT IS APPROXIMATELY 24,000 SQUARE FEET (0.55 ACRES).
3. PER FEMA FIRM PANEL 13121C0083G DATED SEPTEMBER 18, 2013, PORTIONS OF THIS PROJECT ARE LOCATED WITHIN THE 100-YEAR FLOOD ELEVATION.
4. THERE ARE NO WETLANDS LOCATED WITHIN THE PROJECT LIMITS.
5. THE NAME, ADDRESS, AND PHONE NUMBER OF THE PRIMARY PERMITEE IS:

CHRIS BOYD
CITY OF ROSWELL
(770) 817-8750
6. THE 24-HOUR CONTACT FOR EROSION AND SEDIMENT CONTROL IS:

CHRIS BOYD
CITY OF ROSWELL
(770) 817-8750

TREE PRESERVATION/PROTECTION NOTES

1. ALL LIMITS OF CONSTRUCTION AS INDICATED ON THE DRAWINGS SHALL BE CLEARLY IDENTIFIED BY ORANGE SAFETY FENCE PRIOR TO COMMENCEMENT OF ANY LAND DISTURBANCE EXCEPT THOSE OPERATIONS NEEDED TO INSTALL EROSION AND SEDIMENT CONTROL MEASURES.
2. ENGINEER SHALL INSPECT SAFETY FENCING PRIOR TO LAND DISTURBANCE.
3. THE CONTRACTOR SHALL PROTECT ALL TREES AND VEGETATION ON THE SITE EXCEPT AS NOTED ON THE PLANS OR APPROVED BY THE CITY OF ROSWELL ENGINEER OR INSPECTOR.
4. ALL TREE PROTECTION MEASURES SHALL BE INSTALLED PRIOR TO CLEARING AND TRENCHING.
5. ORANGE SAFETY FENCE SHALL BE INSTALLED ALONG THE OUTER EDGE OF AND COMPLETELY SURROUNDING THE CRITICAL ROOT ZONES OF ALL SPECIMEN TREES OR STANDS OF TREES, OR OTHERWISE DESIGNATED TREE PROTECTION ZONES PRIOR TO ANY LAND DISTURBANCE.
6. ALL TREE PROTECTION ZONES SHALL BE DESIGNATED WITH "TREE SAVE AREA" SIGNS.
7. WHEN DIGGING NEAR TREES, THE CONTRACTOR SHALL PRUNE ALL EXPOSED ROOTS 1-INCH IN DIAMETER AND LARGER ON THE SIDE OF THE TRENCH ADJACENT TO THE TREES. PRUNING SHALL CONSIST OF MAKING A CLEAN CUT FLUSH WITH THE SIDE OF THE TRENCH TO PROMOTE NEW ROOT GROWTH.
8. PRUNING OF TREE LIMBS TO PROVIDE CLEARANCE FOR EQUIPMENT AND MATERIALS SHALL BE DONE ACCORDING TO STANDARD ARBORICULTURAL PRACTICES.
9. ALL BUFFERS AND TREE SAVE AREAS ARE TO BE CLEARLY IDENTIFIED WITH PROTECTIVE FENCING PRIOR TO COMMENCEMENT OF ANY LAND DISTURBING ACTIVITY.

CONSTRUCTION SCHEDULE

ACTIVITY	WEEK									
	1	2	3	4	5	6	7	8	9	10
INSTALLATION OF SEDIMENT CONTROL	█									
INSTALLATION OF PIPELINE		█	█	█	█					
MAINTENANCE OF EROSION CONTROL			█	█	█					
TEMPORARY AND PERMANENT GRASSING						█	█	█		
CLEAN-UP									█	

APPROXIMATE START: OCTOBER 2017
APPROXIMATE FINISH: JANUARY 2018

CERTIFICATION

I CERTIFY UNDER PENALTY OF LAW THAT THIS PLAN WAS PREPARED AFTER A SITE VISIT TO THE LOCATIONS DESCRIBED HEREIN BY MYSELF OR MY AUTHORIZED AGENT, UNDER MY DIRECT SUPERVISION.

Pedro M. Rosello

PEDRO M. ROSSELLO, P.E.
LEVEL II CERTIFIED DESIGN PROFESSIONAL #0000019365
EXP. DATE: 12/6/2018

GEORGIA
UNIFORM CODING SYSTEM
FOR SOIL EROSION AND SEDIMENT CONTROL PRACTICES
GEORGIA SOIL AND WATER CONSERVATION COMMISSION

STRUCTURAL PRACTICES

CODE	PRACTICE	DETAIL	MAP SYMBOL	DESCRIPTION
Cd	CHECKDAM			A small temporary barrier or dam constructed across a swale, drainage ditch or area of concentrated flow.
Ch	CHANNEL STABILIZATION			Improving, constructing or installing an open channel, existing stream, or ditch.
Co	CONSTRUCTION EXITS			A roadblock or gate located at the construction site to provide a place for removing mud from the tires of exiting vehicles.
Cr	CONSTRUCTION ROAD STABILIZATION			A roadway constructed as part of a construction plan including access roads, additional roads, parking areas and other on-site vehicle transportation routes.
Dc	STREAM DIVERSION CHANNEL			A temporary channel constructed to convey flow around a construction site while a permanent structure is being constructed.
Di	DIVERSION			An earth channel or dike (excavation, berm, or across a slope to divert runoff). This may be a temporary or permanent structure.
Dn1	TEMPORARY CONFORMANCE STRUCTURE			A flexible barrier of heavy-duty fabric or other material designed to safely conduct surface runoff on a slope. This is temporary and inexpensive.
Dn2	PERMANENT CONFORMANCE STRUCTURE			A rigid curb, pipe, wall, or similar material designed to safely conduct surface runoff on a slope.
Fr	FILTER RING			A temporary stone barrier constructed at stream drain inlets and pond outlets.
Ga	GABION			Rock fill baskets which are hand-poured into position forming self-stabilizing structures.
Gr	GRADE STABILIZATION STRUCTURE			Permanent structures installed to protect channels or waterways when channel erosion would be sufficient to prevent water from being used.
Lv	LEVEL SPREADER			A structure to convert concentrated flow of water into less erosive sheet flow. This should be constructed only on unobstructed beds.
Rd	ROCK FILTER DAM			A permanent or temporary stone filter dam installed across small streams or channels.
Re	RETAINING WALL			A wall installed to stabilize cut and fill slopes where maximum permissible slopes are not obtainable. Each structure will require special design.
Rt	RETRO FITTING			A device or structure placed in front of a permanent stormwater detention pond outlet structure to serve as a temporary sediment filter.
Sd1	SEDIMENT BARRIER			A barrier to prevent sediment from leaving the construction site. It may be a sandbag, bank of trees or logs, logs and poles, gravel, or a silt fence.
Sd2	SILT SEDIMENT TRAP			An impounding area created by narrowing a stream at a sharp angle. The narrowed area will be filled and stabilized on completion of construction activities.
Sd3	TEMPORARY SEDIMENT BASKET			A sign created by excavation or a dam across a waterway. The surface water will be temporarily stored allowing the bulk of the sediment to drop out.
Sd4	TEMPORARY SEDIMENT TRAP			A small temporary pond that traps a disturbed area so that sediment can settle out. The practice features discharging a temporary sediment trap from a temporary sediment basin to the back of a pipe or ditch.
Sk	FLUATING SURFACE SKIMMER			A buoyant device that releases surface water from the surface of sediment ponds, traps, or basins at a controlled rate of flow.
Spb	SEEP BERM			A linear control device constructed as a diversion perpendicular to the direction of soil to enhance dispersion and infiltration, while creating multiple sedimentation chambers with the employment of permeable dikes.

STRUCTURAL PRACTICES

CODE	PRACTICE	DETAIL	MAP SYMBOL	DESCRIPTION
Sr	TEMPORARY STREAM CROSSING			A temporary bridge or culvert-type structure protecting a stream or waterway from damage by creating construction equipment. A stream or waterway shall be closed to all traffic during construction activities.
St	STORMWATER PROTECTION			A barrier or other device to prevent channel or the outlet of a storm drain system from being eroded by the concentrated runoff.
Su	SURFACE SURROUNDING			A rough soil surface with horizontal depressions on a contour or slopes left in a designated condition after grading.
Tc	TURBIDITY CURTAIN			A floating or chained barrier installed within the water (it may also be referred to as a silt curtain, silt barrier, or silt curtain).
Tp	TOPSOILING			The practice of stripping off the more fertile soil, storing it, then spreading it over the disturbed area after completion of construction activities.
Tr	TREE PROTECTION			To protect desirable trees from injury during construction activity.
Wt	VEGETATED WATERWAY OR STORMWATER CONDUITWAY CHANNELS			Planting of vegetative water conduits for diversion, retention, berm, check or similar structures.

VEGETATIVE PRACTICES

CODE	PRACTICE	DETAIL	MAP SYMBOL	DESCRIPTION
Bf	BUFFER ZONE			Strip of undisturbed original vegetation, enhanced or restored existing vegetation or the establishment of vegetation surrounding an area of disturbance or land-use change.
Cs	COASTAL DUNE STABILIZATION (WITH VEGETATION)			Planting vegetation on dunes that are eroded, artificially constructed, or non-existent.
Ds1	DISTURBED AREA STABILIZATION (WITH MULCHING ONLY)			Establishing temporary protection for disturbed areas where seedlings may not have a suitable growing season to produce an erosion-reducing cover.
Ds2	DISTURBED AREA STABILIZATION (WITH TEMP. SEEDING)			Establishing a temporary vegetative cover with fast growing seedlings on disturbed areas.
Ds3	DISTURBED AREA STABILIZATION (WITH PERM. SEEDING)			Establishing a permanent vegetative cover such as trees, shrubs, vines, grasses, or legumes on disturbed areas.
Ds4	DISTURBED AREA STABILIZATION (SODDING)			A permanent vegetative cover using sods on highly erodible or critically eroded beds.
Du	DUST CONTROL ON DISTURBED AREAS			Correcting surface and air movement of dust on construction site, roadways and other sites.
Fl-Cd	FLOCCULANTS AND COAGULANTS			Substances formulated to assist in the solid/liquid separation of suspended particles in water.
Sb	STREAMBANK STABILIZATION (WITH PERM. VEGETATION)			The use of readily available native plant materials to reinforce and enhance streambanks, or to prevent, or reduce and repair severe streambank erosion problems.
Ss	SLOPE STABILIZATION			A protective covering used to prevent erosion and establish temporary or permanent vegetation on steep slopes, shorelines, or ditches.
Tac	TACKLINGS AND BONDING			Substance used to anchor straw or hay matting by causing the organic material to bind together.

04/2000 (Revised - 2011)



ESI
ENGINEERING STRATEGIES, INC.
3855 SHALLOWFORD ROAD, SUITE 525
MARIETTA, GA 30062
(770) 429-0001



DATE: AUGUST 2017
PROJECT NUMBER: —
REVISION

SCALE: 1" = 40' FOR SCALES SHOWN ON THIS SHEET. IF NOT 1" = 40' ON THIS SHEET, ADJUST SCALES ACCORDINGLY.

CITY OF ROSWELL, GEORGIA
MILLBROOK CIR. WATER MAIN REPLACEMENT
EROSION CONTROL NOTES


CERTIFIED EROSION CONTROL DESIGN
PROFESSIONAL NUMBER 0000019365

SHEET NO.



- NOTES:**
1. AVOID LOCATING ON STEEP SLOPES OR AT CURVES ON PUBLIC ROADS.
2. REMOVE ALL VEGETATION AND OTHER UNSUITABLE MATERIAL FROM THE FOUNDATION AREA, GRADE, AND CROWN FOR POSITIVE DRAINAGE.
3. AGGREGATE SIZE SHALL BE IN ACCORDANCE WITH NATIONAL STONE ASSOCIATION R-2 (1.5"-3.5" STONE).
4. GRAVEL PAD SHALL HAVE A MINIMUM THICKNESS OF 6".
5. PAD WIDTH SHALL BE EQUAL FULL WIDTH AT ALL POINTS OF VEHICULAR EGRESS, BUT NO LESS THAN 20'.
6. A DIVERSION RIDGE SHOULD BE CONSTRUCTED WHEN GRADE TOWARD PAVED AREA IS GREATER THAN 2%.
7. INSTALL PIPE UNDER THE ENTRANCE IF NEEDED TO MAINTAIN DRAINAGE DITCHES.
8. WHEN WASHING IS REQUIRED, IT SHOULD BE DONE ON AN AREA STABILIZED WITH CRUSHED STONE THAT DRAINS INTO AN APPROVED SEDIMENT TRAP OR SEDIMENT BASIN (DIVERT ALL SURFACE RUNOFF AND DRAINAGE FROM THE ENTRANCE TO A SEDIMENT CONTROL DEVICE).
9. WASHRACKS AND/OR TIRE WASHERS MAY BE REQUIRED DEPENDING ON SCALE AND CIRCUMSTANCE. IF NECESSARY, WASHRACK DESIGN MAY CONSIST OF ANY MATERIAL SUITABLE FOR TRUCK TRAFFIC THAT REMOVE MUD AND DIRT.
10. MAINTAIN AREA IN A WAY THAT PREVENTS TRACKING AND/OR FLOW OF MUD ONTO PUBLIC RIGHTS-OF-WAYS. THIS MAY REQUIRE TOP DRESSING, REPAIR AND/OR CLEANOUT OF ANY MEASURES USED TO TRAP SEDIMENT.

CRUSHED STONE CONSTRUCTION EXIT
Co



- NOTES:**
1. USE TRENCHER (I.E. DITCH WHICH) TO CUT A 4" x 5" x 18" D TRENCH ALONG DRIP LINE (LIMIT OF CLEARING) AND BACKFILL WITH SAND AND LIGHTLY COMPACT.
2. SPACE STAKES AT INTERVALS SUFFICIENT TO MAINTAIN ALL FENCING OUT OF DRIP LINE OR AS SHOWN BY ENGINEER (SET STAKES NO GREATER THAN 6 FEET ON CENTER-REBAR IS NOT TO BE USED FOR STAKES).
3. MAINTAIN FENCE BY REPAIRING AND/OR REPLACING DAMAGED FENCE. DO NOT REMOVE FENCING PRIOR TO LANDSCAPING OPERATIONS.
4. DO NOT STORE OR STACK MATERIALS, EQUIPMENT, OR VEHICLES WITHIN FENCED AREA.
5. FENCE SHALL BE ORANGE VINYL "SNOW FENCE" 4' HIGH MINIMUM.

TREE PROTECTION - "SNOW" FENCE
Tr

SILTY FENCE - TYPE SENSITIVE
Sd1-S

CURB INLET FILTER "PIGS IN BLANKET"
Sd2-P

EROSION, SEDIMENTATION & POLLUTION CONTROL PLAN CHECKLIST
STAND ALONE CONSTRUCTION PROJECTS

SWCD: City of Roswell, GA
Project Name: Millbrook Circle WM Replacement Address: 100 Millbrook Cir., Roswell, GA 30075
City/County: Roswell/Fulton Date on Plans: August 2017

TO BE SHOWN ON ES&PC PLAN

Plan Page #	Included Y/N	Description
7	Y	1 The applicable Erosion, Sedimentation and Pollution Control Plan Checklist established by the Commission as of January 1 of the year in which the land-disturbing activity was permitted. (The completed Checklist must be submitted with the ES&PC Plan or the Plan will not be reviewed.)
6	Y	2 Level II certification number issued by the Commission, signature and seal of the certified design professional. (Signature, seal and Level II number must be on each sheet pertaining to ES&PC Plan or the Plan will not be reviewed.)
NA	NA	3 Limits of disturbance shall be no greater than 50 acres at any one time without prior written authorization from the EPD District Office. If EPD approves the request to disturb 50 acres or more at any one time, the plan must include at least 4 of the BMPs listed in Appendix 1 of this checklist. (A copy of the written approval by EPD must be attached to the plan for the plan to be reviewed.)
6	Y	4 The name and phone number of the 24-hour local contact responsible for erosion, sedimentation and pollution controls.
6	Y	5 Provide the name, address and phone number of primary permittee.
6	Y	6 Note total and disturbed acreage of the project or phase under construction.
NA	NA	7 Provide the GPS location of the construction exit for the site. Give the Latitude and Longitude in decimal degrees.
6	Y	8 Initial date of the Plan and the dates of any revisions made to the Plan including the entity who requested the revisions.
6	Y	9 Description of the nature of construction activity.
6	Y	10 Provide vicinity map showing site's relation to surrounding areas. Include designation of specific phase, if necessary.
6	Y	11 Identify the project receiving waters and describe all sensitive adjacent areas including streams, lakes, residential areas, wetlands, marshlands, etc. which may be affected.
6	Y	12 Design professional's certification statement and signature that the site was visited prior to development of the ES&PC Plan as stated on page 15 of the permit.
NA	NA	13 Design professional's certification statement and signature that the permittee's ES&PC Plan provides for an appropriate and comprehensive system of BMPs and sampling to meet permit requirements as stated on page 15 of the permit.
NA	NA	14 Clearly note the statement that "The design professional who prepared the ES&PC Plan is to inspect the installation of the initial sediment storage requirements and perimeter control BMPs within 7 days after installation."
6	Y	15 Clearly note the statement that "Non-exempt activities shall not be conducted within the 25 or 50-foot undisturbed stream buffers as measured from the point of vested vegetation or within 25-feet of the coastal marshland buffer as measured from the Jurisdictional Determination Line without first acquiring the necessary variances and permits."
NA	NA	16 Provide a description of any buffer encroachments and indicate whether a buffer variance is required.

NA	17 Clearly note the statement that "Amendments/revisions to the ES&PC Plan which have a significant effect on BMPs with a hydraulic component must be certified by the design professional."	
NA	18 Clearly note the statement that "Waste materials shall not be discharged to waters of the State, except as authorized by a section 404 permit."	
6	Y	19 Clearly note statement that "The escape of sediment from the site shall be prevented by the installation of erosion and sediment control measures and practices prior to land disturbing activities."
6	Y	20 Clearly note statement that "Erosion control measures will be maintained at all times. If full implementation of the approved plan does not provide for effective erosion control, additional erosion and sediment control measures shall be implemented to control or treat the sediment source."
6	Y	21 Clearly note the statement "Any disturbed area left exposed for a period greater than 14 days shall be stabilized with mulch or temporary seeding."
NA	NA	22 Any construction activity which discharges storm water into an Impaired Stream Segment, or within 1 linear mile upstream and within the same watershed as, any portion of an Impaired Stream Segment must comply with Part III. C. of the Permit. Include the completed Appendix 1 listing all the BMPs that will be used for those areas of the site which discharge to the Impaired Stream Segment."
NA	NA	23 If a TMDL Implementation Plan for sediment has been finalized for the Impaired Stream Segment (identified in item 22 above) at least six months prior to submittal of NOI, the ES&PC Plan must address any site-specific conditions or requirements included in the TMDL Implementation Plan."
NA	NA	24 BMPs for concrete washdown of tools, concrete mixer chutes, hoppers and the rear of the vehicles. Washout of the drum at the construction site is prohibited."
6	Y	25 Provide BMPs for the remediation of oil petroleum spills and leaks.
NA	NA	26 Description of the measures that will be installed during the construction process to control pollutants in storm water that will occur after construction operations have been completed."
NA	NA	27 Description of the practices that will be used to reduce the pollutants in storm water discharges."
6	Y	28 Description and chart or timeline of the intended sequence of major activities which disturb soils for the major portions of the site (i.e., initial perimeter and sediment storage BMPs, clearing and grubbing activities, excavation activities, utility activities, temporary and final stabilization).
NA	NA	29 Provide complete requirements of inspections and record keeping by the primary permittee."
NA	NA	30 Provide complete requirements of sampling frequency and reporting of sampling results."
NA	NA	31 Provide complete details for retention of records as per Part IV.F. of the permit."
NA	NA	32 Description of analytical methods to be used to collect and analyze the samples from each location."
NA	NA	33 Appendix B rationale for NTU values at all outfall sampling points where applicable."
NA	NA	34 Delineate all sampling locations, perennial and intermittent streams and other water bodies into which storm water is discharged."
NA	NA	35 A description of appropriate controls and measures that will be implemented at the construction site including: (1) initial sediment storage requirements and perimeter control BMPs, (2) intermediate grading and drainage BMPs, and (3) final BMPs. For construction sites where there will be no mass grading and the initial perimeter control BMPs, intermediate grading and drainage BMPs, and final BMPs are the same, the plan may combine all of the BMPs into a single phase."
2,3	Y	36 Graphic scale and North arrow.
2,3	Y	37 Existing and proposed contour lines with contour lines drawn at an interval in accordance with the following:

Map Scale	Ground Slope	Contour Intervals, ft.
1 inch = 100ft or larger scale	Flat 0 - 2% Rolling 2 - 8% Steep 8% +	0.5 or 1 1 or 2 2.5 or 10

38 Use of alternative BMPs whose performance has been documented to be equivalent to or superior to conventional BMPs as certified by a Design Professional (unless disapproved by EPD or the Georgia Soil and Water Conservation Commission). Please refer to the Alternative BMP Guidance Document found at www.gaswcc.org.

39 Use of alternative BMP for application to the Equivalent BMP List. Please refer to Appendix A-2 of the Manual for Erosion & Sediment Control in Georgia 2016 Edition.

40 Delineation of the applicable 25-foot or 50-foot undisturbed buffers adjacent to state waters and any additional buffers required by the Local Issuing Authority. Clearly note and delineate all areas of impact.

41 Delineation of on-site wetlands and all state waters located on and within 200 feet of the project site.

42 Delineation and acreage of contributing drainage basins on the project site.

43 Provide hydrology study and maps of drainage basins for both the pre- and post-developed conditions."

44 An estimate of the runoff coefficient or peak discharge flow of the site prior to and after construction activities are completed.

45 Storm-drain pipe and weir velocities with appropriate outlet protection to accommodate discharges without erosion. Identify/Delineate all storm water discharge points.

46 Soil series for the project site and their delineation.

47 The limits of disturbance for each phase of construction.


48 Provide a minimum of 67 cubic yards of sediment storage per acre drained using a temporary sediment basin, retrofitted detention pond, and/or excavated inlet sediment traps for each common drainage location. Sediment storage volume must be in place prior to and during all land disturbance activities until final stabilization of the site has been achieved. A written justification explaining the decision to use equivalent controls when a sediment basin is not attainable must be included in the plan for each common drainage location in which a sediment basin is not provided. A written justification as to why 67 cubic yards of storage is not attainable must also be given. Worksheets from the Manual included for structural BMPs and all calculations used by the storage design professional to obtain the required sediment when using equivalent controls. When discharging from sediment basins and impoundments, permittees are required to utilize outlet structures that withdraw water from the surface, unless infeasible. If outlet structures that withdraw water from the surface are not feasible, a written justification explaining this decision must be included in the plan.

49 Location of Best Management Practices that are consistent with and no less stringent than the Manual for Erosion and Sediment Control in Georgia. Use uniform coding symbols from the Manual, Chapter 6, with legend.

50 Provide detailed drawings for all structural practices. Specifications must, at a minimum, meet the guidelines set forth in the Manual for Erosion and Sediment Control in Georgia.

51 Provide vegetative plan, noting all temporary and permanent vegetative practices. Include species, planting dates and seeding, fertilizer, lime and mulching rates. Vegetative plan shall be site specific for appropriate time of the year that seeding will take place and for the appropriate geographic region of Georgia.

* If using this checklist for a project that is less than 1 acre and not part of a common development but within 200 ft of a perennial stream the * checklist items would be NA. **Effective January 1, 2017**




NOTES:
1. IN ADDITION TO THIS SIGN, A TEMPORARY WATER SUPPLY WITH A WATER HOSE, SHALL BE INSTALLED AT ALL CONSTRUCTION SITE EXITS.
2. SIGN MATERIALS TO BE, NOT LESS THAN 1/2" DURA-PLY PLYWOOD.
3. SIGN LETTERING TO BE "UPPER CASE" TYPICAL.

City of Roswell
ENGINEERING DIVISION
30 Hill St., Ste. G-30 Roswell, Ga. 30075 (770-641-3768)

CONSTRUCTION EXIT SIGN
SCALE: 1" = 1'-0" AutoCAD 2000.dwg
DATE: FEB. 4, 1997 REVISION: 12-09-03
DRAWN: S. HAMBY DWG. #: 109-001

CERTIFIED EROSION CONTROL DESIGN
PROFESSIONAL NUMBER 0000019365



ESI
ENGINEERING STRATEGIES, INC.
3855 SHALLOWFORD ROAD, SUITE 525
MARIETTA, GA 30067
(770) 429-6001

PROJECT NUMBER: —

DATE:	REVISION:
AUGUST 2017	

DATE: AUGUST 2017

REVISION: —

DSGN: —
DRWN: —
CHK: —

BAR BELOW IS 1" LONG FOR SCALES SHOWN ON THIS SHEET. IF NOT 1" LONG ON THIS SHEET, ADJUST SCALES ACCORDINGLY.

CITY OF ROSWELL, GEORGIA
MILLBROOK CIR. WATER MAIN REPLACEMENT
EROSION CONTROL DETAILS

SHEET NO.